made at your expense from other sources in addition to the levy of a penalty of 3 per cent of the value of the order as and by way of liquidated damages. In such an event the Stores Purchase Committee reserve the right to remove your name from the list of approved firms.

The quotations should be superscribed "Quotations for P. S. Tank for Kalkunike Water Supply" with the above enquiry Number.

This enquiry will be closed on the 31st March 1938.

Schedule.

Item No.	Description of material offered	Quantity	Price quoted F. O. R.	Time of delivery
	Pressed steel tank 12′×8′×8′ covered (capacity 4,800 gallons) made up of standard pressed steel unit plates 4 ft. square with ¼″ thick plates for bottom and 3/16″ for top stroke with suitable internal bracings, inside and outside ladders and provided with water level indicator. Roof should be flat and of ⅛″ black plates and provided with a recessed manhole complete with locking arrangement. Two beams 8″×4″ in section and five joists 6″×3″ are also to be provided to support the tank	One.	Mysore.	

Yours faithfully,
T. RANGASWAMI,
Secretary,
Stores Purchase Committee.

No. S. P. C. 20976-21000, *dated* 18*th March* 1938.

NOTICE.

DISTRIBUTION TRANSFORMERS REQUIRED FOR DAVANGERE AND OTHER TOWNS.

Enquiry No. 2745. E. D. 531.

Sealed tenders will be received by the Secretary, Stores Purchase Committee, for the supply of 84 Distribution Transformers required for Davangere and other towns up to 18th May 1938.

Intending tenderers may, on application to the Secretary, Stores Purchase Committee, obtain the requisite tender forms on which tenders should be submitted. Applications should be accompanied by a cash remittance of Rs. 10 which is the price fixed for a set of forms and which is not refundable.

Cheques and postage stamps will not be accepted towards the cost of forms nor will the forms be sent by V. P. P.

By Order,
T. RANGASWAMI,
Secretary,
Stores Purchase Committee.

BUILDINGS DIVISION, BANGALORE.

Notification dated 21*st*—22*nd March* 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 9th April 1938, up to 2-30 P.M. for constructing a Primary School building at Reserve Police Lines to the east of Guard House, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 350 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Primary School Building at Reserve Police Lines to the east of Guard House, Bangalore in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department, or those fixed by the Executive Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a Primary School (to the use of Guard House) at the Reserve Police Lines, Bangalore.

Item No.	Description of work	No.	Rate	Contents	Total
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 3 6	122	
2	Stone jelly concrete in lime mortar	C.ft.	0 3 6	1,169	
3	Burnt size stone in clay with bond stones at 6′ apart for foundation and basement	C.ft.	0 3 6	2,646	
4	Burnt brick in clay superstructure	C.ft.	0 3 3	4,043	
5	Burnt stone slabs 6″ thick, 2 lines dressed to exposed portions and rough dressing to top surface	S.ft.	0 6 0	1,117	
6	Archwork with wire-cut brick in lime mortar	C.ft.	0 10 0	49	
7	Burnt brick in lime mortar	C.ft.	0 4 0	824	
7(a)	Plastering with lime mortar	Sqr.	3 0 0	69·63	
8	Wire-cut brick in lime mortar, pillars with lime mortar plastering, 1½′ at bottom with tops as per plan, 11′ high with base and capital complete	Each	15 0 0	12	
9	Tata's tested R.S. girders with cutting, lifting, hoisting and boxing with terrace bricks in cement mortar and painting at bottom	Cwt.	13 0 0	46·52	
10	R. B. C. roofing single course brick with iron rods and concrete 7″ depth and surki concrete at top with 2 courses of flat tiles and plastering in lime mortar	Sqr.	60 0 0	21·84	
11	Plain cornice with 6″ deep with coloured cement plastering	R.ft.	0 4 0	250	
12	Ornamental parapet wall as per design	R.ft.	0 8 0	240	
13	Coping over compound in lime mortar	R.ft.	0 6 0	20	

Item No.	Description of work	No.	Rate	Contents	Total
			Rs. a. p.		Rs.
14	Flooring with 1½" cement concrete with red cement finish mortar concrete with baby jelly on 3" stone jelly concrete with 1' depth of boulders for damp proof course	Sqr.	0 0 28	17·34	
15	Flooring for door ways with ½" to 1½" jelly with cement mortar and plaster with red cement finish	Sqr.	0 0 15	0·34	
16	Skirting with square tiles in lime mortar and cement plastering and red cement finish as per design (9"×1½")	R.ft.	0 0 4	328	
17	Collapsible gate with frame etc., and fixing with painting, etc., complete	S.ft.	0 0 2	104	
18	T. W. panelled doors with frame and shutters 1¼" thick with iron fittings and painting, etc. with glazed shutters to top ventilators about 2' dia semicircular	S.ft.	0 0 8	106	
19	T. W. windows outside panelled shutters and inside glassed shutters and top 1½ ventilators with glazed shutters as per plan and iron bars painting and iron fittings, etc.	S.ft.	0 0 4	160	
20	T. W. ventilators with glazed shutters and iron bars etc., complete with painting	S.ft.	0 0 1	50	
21	T. W. gate with iron fittings and painting complete	S.ft.	1 8 0	40	
22	White and colour washing as per plastering ..	Sqr.	0 5 0	69·63	
23	Cement pointing to basement	Sqr.	3 0 0	4·25	
24	Coving works at bottom of roofing	R.ft.	0 2 0	597	
25	Ornamental works and balusters in front and west side and unforeseen works ..	..	LS.		
26	Levelling ground	..	LS.		
27	Zinc water down pipes 4" dia.	R.ft.	0 4 0	256	
28	Wall and board with painting	..	LS.		

B. R. GARUDACHAR,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 14th March 1938.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 4th April 1938, for improvements to Epidemic Diseases Hospital, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for improvements to Epidemic Diseases Hospital, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 170 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 4th April 1938 at 4 P.M. The final acceptance of the tender will rest with the Assistant Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for the current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of May 1938, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 10 per day, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

NOTE.—(*A*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliance for hoisting.

(3) Provide mortar mill and shed to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) provide arrangements for pumping and baling from excavations and foundations, wherever and whenever necessary, with their own pumping apparatus including necessary leading drains, slump pits, etc.,

(9) wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.,

(10) afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

NOTE.—(*B*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 1,700 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore Teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″ ..	3	4	0	,,
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	,,
(3) Planks 1″ to 1¾″ to required sizes ..	4	8	0	,,

Approximate estimated quantities for improving Epidemic Diseases Hospital, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Removing and resetting Cuddapah slab flooring on fresh mortar bed and cement pointing, etc., complete	Sqr.	..	9·41	
2	Cement pointing to flooring tiles, replacing broken ones on mortar bed, etc., complete ..	,,	..	9·56	
3	Replacing T.W. windows with panelled shutters as per existing design with necessary iron fixtures in place of demaged ones including dismantling masonry, etc., complete ..	S.ft.	..	170	
4	Providing an incinerator as per specification and design for destruction of infective materials with chimney arrangements, etc., complete	No.	..	1	
5	Earthwork excavation for foundation in hard gravelly soil and filling basement and tamping	C.yd.	..	6	
6	Burnt brick in lime mortar 1 : 2 for foundation and basement	C.ft.	..	144	
7	Burnt brick in clay for superstructure ..	,,	..	346	
8	Burnt stone slabs 6″ thick roughly dressed and fixed in mortar bed	S.ft.	..	103	
9	Plastering with chunam mortar ½″ thick including rounding of corners (convex corners being of cement mortar 1 : 4 for a width of 3″ both sides)	Sqr.	..	36·93	
10	Cement plastering ½″ thick	,,	..	1·96	
11	T.W. work wrought and put up including wood-oiling, etc. complete	C.ft.	..	40·55	
12	Roofing with Mangalore pattern Yelhanka tiles on teak reapers 2″×1″, etc., complete ..	Sqr.	..	23·64	
13	Providing ridge tiles set in mortar and cement pointing	R.ft.	..	80	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
14	Flooring with 1½″ cement concrete (1 : 2 : 4) on 3″ lime concrete (jelly to be of granite metal) with toping of red coloured cement ¼″ thick finished with ironite 2½ lbs. per square and cut to tile pattern where required with all corners rounded, etc., complete	Sqr.	..	2·65	
15	Chocolate painting 2 coats	,,	..	0·53	
16	White and colour washing including scraping wherever necessary	,,	..	13·25	
17	Chunam borders with burnt brick in mortar ¾′ thick over roof end including chunam plastering, white washing, etc., complete ..	R.ft.	..	83	
18	Constructing sink in the bath room 5′×4′ including burnt stone slab flooring sides to be of brick masonry and cement plastered, etc., complete	Each	..	18	
19	Providing T.W. wall shelves panelled of ½″ thick planks with shutters including four cross planks of 1½″ thick 1′ wide with superior brass locks and handles and brass fittings, etc., complete	S.ft.	..	22½	
20	Providing chimney to the bath room with necessary masonry work including oven smoke escape, etc., complete	Each	..	1	
21	Providing and fixing new T.W. windows with 3″×5″ frames and 1¼″ thick shutters as per existing design including iron fixtures, etc., complete	S.ft.	..	10	
22	Removing and refixing the existing zinc sheet roof with necessary repairs including bolts, nuts, etc., complete	Sqr.	..	9·00	
23	Under pinning the damaged basement with burnt brick in chunam mortar 1 : 2 including cement pointing, etc., complete	C.ft.	..	680	
24	Providing and fixing new T.W. battened door in place of old one with frames 3″×5″ with 1½″ thick shutters and iron fixtures as per existing design, etc., complete, including dismantling the old door	S.ft.	..	21	
25	Constructing supporting pillars with burnt brick in mortar 1 : 2 including chunam plastering, white or colour washing, etc., complete ..	C.ft.	..	13	
26	Constructing a drain for conservancy burnt brick in composite mortar on cement concrete bed 3″ thick including cement plastering ½″ thick and rounding of corners, etc., complete	R.ft.	..	450	
27	Cement pointing to ridge tiles of Quarters ..	,,	..	340	
28	Providing and fixing fly proof shutters as per required specification and design to windows of Operation Theatre with iron fixtures, etc., complete	S.ft.	..	30	
29	Providing and fixing glazed shutters as per requirements to windows of Operation Theatre with iron fixtures, etc., complete ..	,,	..	30	

Notification dated 18th March 1938.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 4th April 1938, for constructing Pathology Block in the premises of Krishnarajendra Hospital, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for Constructing Pathology Block in the Premises of Krishnarajendra Hospital, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 2,360 only in cash or Government Security, Municipal Debentures, Post Office Cash Certificates, (at cash payment value at the time of deposits and not face value) as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 4th April 1938 at 4 P.M. The final acceptance of the tender will rest with the Government which does not bind itself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for the current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department within seven months, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 50 per day, which will be recovered, from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant

Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Note.—(A) The contractor should at his own cost—

(1) provide rods, stakes, ropes and labours required in setting out the works,
(2) provide all necessary scaffolding, centering labour and appliance for hoisting,
(3) provide mortar mill and shed to keep materials under cover and also for workmen,
(4) arrange for protecting work during inclement weather,
(5) supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work,
(6) supply all water required for work and workmen and shall provide latrines, drainages, etc.,
(7) clean away all dirt, rubbish, superfluous materials and debris as they accumulate,
(8) provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with their own pumping apparatus, including necessary leading drains, slump pits, etc.,
(9) wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.,
(10) afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note.—(B) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 8,000 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″	3	4	0	„
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	„
(3) Planks 1″ to 1¾″ to required sizes	4	8	0	„

Abstract estimate for the Pathology Block in the premises of the Krishnarajendra Hospital, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Ground Floor.				
1	Earthwork excavation in hard gravelly soil for foundation and filling in basement with watering and consolidations	C.yd.		491	
2	Filling in foundation with broken granite stone jelly concrete in lime mortar 1 : 2 : 4 with tamping in layers of not more than 6″ thick including watering, etc.	C.ft.		4,483	
3	Burnt size stone in lime mortar with bond stones 6′ apart for foundations	„		5,933	
4	Do do including all quoins neatly dressed 2′ wide for basement	„		2,181	
5	Burnt stone slabs 6″ thick for outer walls of basement and steps including two line dressing on exposed faces and one line dressing on all other faces	Sq.ft.		756	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
6	Burnt stone slabs 6″ thick one line dressed on all faces for all inner walls of basement, cill and lintel of doors and windows, ventilators and below girders and stone plates below R.C.C. roofs	Sq.ft.	..	2,478	
7	Burnt brick in lime mortar for superstructure	C.ft.	..	9,001	
8	Wire-cut brick in cement mortar 1 : 3 for piers and pillars, etc.	,,	..	1,023	
9	Wire-cut brick in cement mortar 1 : 3 for arch work	,,	..	274	
10	Burnt brick in lime mortar for arch work	,,	..	267	
11	Partition wall with burnt brick in cement mortar 1 : 3 with hoop iron or other wall reinforcements in every third course 4½″ thick including plastering and white washing	Sq.ft.	..	2,052	
12	Plastering with chunam mortar (smooth) including rounding of corners (convex corners being of cement mortar 1 : 4) for a width of 3″ both sides and the plaster on the outer face being ground with yellow ochre to a cream tint	Sqr.	..	191·53	
13	Pointing the basement with snowcrete 1 : 3 of sand, and lining neatly	,,	..	8·36	
14	White and colour washing two coats	,,	..	199·89	
15	R.C.C. pillars 14″ diameter at bottom 12″ diameter at top and 12½′ high with the required moulding and plastering for base and capital, etc., complete	Each	..	6	
16	Providing tested rolled steel girders as per B.S.S. including lifting and hoisting and boxing with cement mortar and terrace brick, reinforced with galvanized steel textied from above with one coat of anticorrosive paint and fixing girders with cement concrete in walls, etc., complete	Cwt.	..	209	
17	Roofing with hollow or solid reinforced concrete beams and slabs 1 : 2 : 4 with ceiling flush with bottom flange of girders spaced about 8′ apart to take a super load of 100 lbs. with an extra granolithic floor finish of 1½″ on top with surfacing of red cement ⅜″ thick and with ironite or carborandum (2½ lbs. per square) cut to design of tiles and with expansion joints where necessary and laid to gentle slope with ceiling plastered with finely ground lime mortar mixed with cement as per design with coving and offsets	Sqr.	..	66·98	
18	Flooring with 1½″ cement concrete (1 : 2 : 4) jelly to be of granite metal over 6″ lime concrete bed with topping of red cement ¼″ thick finished with ironite 2½ lbs. per square, and cut to the required tile pattern where required with all corners rounded	Sqr.	..	56·94	
19	Skirting of 1″ thick cement concrete 1 : 2 : 4 with topping of ¼″ thick red cement 9″ high for interior wall as per design	R.ft.	..	872	
20	R.C.C. Chajja 4″ thick for windows 4′ width with anchorage into walls 1½′	S.ft.	..	770	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
21	Teakwood newel staircase 12″ tread 6″ rise on cut stringers with platforms, width of step 5′ including ceiling with ¾″ thick planks, etc., complete with delux varnish two coats for ceiling, etc., including teakwood hand railings with wrought iron flat and square vertical bars as per design with top and bottom rails 3″×5″ and duco finish for hand rails (measurement as per visible tread area)	Sq. ft.	..	160	
22	Teakwood doors with frames 3″×5″ without bottom cills having ⅓ panelled ⅔ glazed (Pilkingtons pin-headed glass ⅛″ thick) 1½″ thick shutters including acme brass fittings rim door locks with handles three finger plates 12″×4″ as per design with six 6″ steel tipped brass hinges and two 6″ hooks, brass screws, barrel bolts of suitable size, etc., including delux varnish two coats	,,	..	562	
23	Teakwood windows 3″×5″ frame with 1¼″ thick glazed shutters in four halves including brass hinges, hooks 2″ rings complete including two coats of green paint outside and two coats of stained polish inside	,,	..	870	
24	Teakwood ventilators with 3″×4″ frame with 1¼″ thickglazed shutters in two halves including fittings and paintings as per item No. 23	,,	..	53	
25	Paving with burnt stone slabs 4″ thick two line dressed, 2′ wide alround the building outside over a gravel bed of 3″ thick pointing with cement, etc., complete	,,	..	620	
26	R.C.C. wall 10″ thick in the curved end with R.C. pillars 6″×10″ spaced 5′ centre to centre including plastering, etc., complete	C.ft.	..	300	
	First Floor.				
1	Burnt brick in lime mortar	C.ft.	..	12,500	
2	Wire cut brick in cement mortar 1 :3	,,	..	1,229	
3	Burnt stone slabs 6″ thick one line dressed on all faces for lintels of doors cills and lintels of windows and ventilators and perforated ventilators bed plates below girders and stone plates below R.C.C. roof as in ground floor	Sq.ft.	..	1,216	
4	Partition wall with burnt brick in cement mortar and with hoop iron or other wall reinforcement in every third course 4½″ thick including plastering and white-washing	,,	..	759	
5	Plastering with chunam mortar for walls including rounding of all corners (convex corners being of cement mortar 1 : 4) for a width of 3″ both sides	Sqr.	..	190.21	
6	White and colour washing two coats	,,	..	190.21	
7	Providing tested rolled steel girders as per B.S.S. including lifting, hoisting and boxing with cement mortar and terrace bricks reinforced with galvanized (steel-tex) tied from above with one coat of anti-corrosive paint and fixing girders with cement concrete on walls.	Cwt.	..	275	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
8	Roofing with hollow or solid reinforced concrete beams and slabs 1 : 2 : 4 with ceiling flush, with bottom flanges of girder spaced about 8′ apart to take a super load of 80 lbs., with ceiling plastered as per design with coving and offsets and on top with surki concrete 4″ thick with two coats of flat tiles plastered smooth complete ..	Sqr.		59·15	
9	Providing sky-lights to the halls with glass panes at the top of roof level as per section..	,,	..	1·60	
10	Skirting of 1″ thick cement concrete 1 : 2 : 4 with topping of ¼″ red cement 9″ high for interior walls as per design ..	R.ft.		834	
11	R.C.C. chajja over windows 4″ thick 4′ width with an anchorage of 1½′ into the walls as per design ..	Sq.ft.		1,034	
12	Teakwood hand railing with wrought iron, flat and square, vertical bars with top and bottom rails 3″×5″ including Duco finish for hand rails ..	R.ft.		79	
13	Plain parapet wall 9″ thick 1½′ to 2′ high as per design including plastering with chunam mortar and white washing, etc., complete ..	R.ft.		264	
14	Providing and fixing cast iron down water pipes of 4″ dia, with suitable bends, etc., complete ..	R.ft.		840	
15	Providing and fixing teakwood doors with frames 3″×5″ without bottom cills having ⅓ panelled ⅔ glazed (Pilkingtons pin-headed ⅛″ glass) 1½″ thick shutters including acme fittings, rim door locks with handles, three finger plates 12″×4″ as per design with six, 6″ steel tipped brass hinges two 6″ hooks brass screws, barrel bolts of suitable size, etc., including delux varnish two coats ..	Sq.ft.		572	
16	Providing and fixing teakwood windows 3″×5″ thick frames with 1¼″ thick glazed shutters in four halves with iron bars ¾″ dia. at 4″ apart including brass fittings, hooks, 2″ rings and casements adjusting stays, etc., complete including two coats of delux varnish ..	,,		455	
17	Providing and fixing teakwood ventilators 3″×4″ thick with 1¼″ thick glazed shutters in two halves with fittings as in item No. 16.	,,		18	
18	Cement perforated ventilators as per design 1½″ thick with 2″×2″ framework above windows ..	,,		40	

M. A. RAMANUJAM,
Assistant Engineer.

KRISHNARAJSAGAR DIVISION.

Notice dated 17th March 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Krishnarajsagar Division, Krishnarajsagar, up to 2 P.M., on Saturday the 9th April 1938, for Constructing Revenue Sub-Division Officer's Quarters at French Rocks.

2. Tenders in the prescribed form, obtainable from the Office of the Executive Engineer, Krishnarajsagar Division, should be addressed to the Executive Engineer, Krishnarajsagar